



A. PROVIDE $9\frac{1}{4}$ " X $24\frac{1}{4}$ " WALL OPENING AND BACKING (1) TO ACCEPT CABINET. MINIMUM $3\frac{1}{4}$ " DEPTH FROM FINISHED WALL.

B. DRILL HOUSING (2) TO LOCATE MOUNTING POINTS WHERE BACKING EXISTS. REMOVE HOUSING (2) AND INSTALL WALL ANCHORS (3) (BY OTHERS) AS REQUIRED FOR WALL/TYPE BACKING.

C. INSTALL EXTINGUISHER CABINET HOUSING (2) INTO WALL OPENING (1).

D. FASTEN HOUSING (2) INTO WALL USING SCREWS TO SUIT WALL CONSTRUCTION (BY OTHERS).

IMPORTANT! AFTER INSTALLATION, ALL JOINTS REQUIRE SECURITY SEALANT BY INSTALLER TO ELIMINATE GAPS BETWEEN WALL AND FIXTURE.

LOCATE ITEM TO CONFORM WITH APPLICABLE CODES FOR ACCESSIBILITY.



NOTE: WEIGHT WITHOUT FIRE EXTINGUISHER = 13 lbs.

____[83] MINIMUM DEPTH

WALL OPENING

WHITEHALL MANUFACTURING
P.O. BOX 3527 Industry, CA 91744
15125 Protor Ave Industry, CA 91744
(628) 968-6681 FAX (626) 855-4862

MANUFACTURE RESISTANT SEMI-RECESSED FIRE EXTINGUISHER CABINET WH1724-A

MANUFACTURE DATE
AUGUST 2018
TO PRESENT

MANUFACTURE RESISTANT SEMI-RECESSED FIRE EXTINGUISHER CABINET WH1724-A

DATE ISSUED
DATE REVISED

DATE REVISED

DATE REVISED

9918-136-001